

ESTOLGA ATTACHMENT SYSTEM, WITHOUT EXPOSED FASTENER IS MAKING FABRICATION AND INSTALLATION MUCH MORE EFFICIENT.
PROJECTS ARE COMPLETED IN 1/3 OF THE TIME.

ALUMINUM COMPOSITE PANELS AND COLUMNS INSTALLATION INSTRUCTIONS

GENERAL NOTES		PANEL LABELS																
<p>THESE INSTRUCTIONS ARE GENERAL IN SCOPE AND FORM, PANELS / COLUMNS ARE TO BE HANDLED AND STORED IN ACCORDANCE WITH SHEET T-1 AND H-1 OF THIS DRAWING SET THROUGHOUT THE INSTALLATION PROCESS. FAILURE TO COMPLY WITH THE INSTRUCTIONS LISTED ON THE INSTALLATION INSTRUCTIONS AND HANDLING MANUAL MAY RESULT IN STRUCTURAL AND VISUAL DISTORTIONS IN THE PANEL / COLUMN SURFACE AND COMPROMISE THE STRUCTURAL INTEGRITY OF THE PANEL / COLUMN SYSTEM, ALLIED METAL IS NOT RESPONSIBLE FOR ANY VISUAL, STRUCTURE AND WATER / AIR INFILTRATION PROBLEMS THAT OCCUR DO TO IMPROPER HANDLING, STORAGE AND INSTALLATION OF THE PANEL / COLUMN SYSTEM.</p>		<p>LETTERS NOTE PANEL TYPE</p> <p>A-1</p> <p>NUMBERS NOTES INSTALLATION ORDER</p>																
INSTALLATION INSTRUCTIONS		STEP 2: FIRST PANEL ALIGNMENT AND INSTALLATION																
<p>STEP 1: SUBSTRATE INSPECTION</p> <p>1 - INSPECT ALL SURFACE(S) TO RECEIVE THE PANELS FOR DAMAGE, DEFECTIVE MATERIAL, PRODUCTS AND IMPROPER INSTALLATION METHODS. ALL DAMAGE, DEFECTIVE MATERIAL, PRODUCTS AND IMPROPER INSTALLATION IS TO BE REPORTED IMMEDIATELY TO THE JOB SUPERVISOR, GENERAL CONTRACTOR, CONSTRUCTION MANAGER, OWNER, OR SUPERVISING COMPANY / PERSON. PANEL INSTALLATION IS TO NOT BEGIN UNTIL ALL OF THE AFOREMENTIONED ISSUES HAVE BEEN FIXED.</p> <p>2 - INSPECT ALL SURFACES TO RECEIVE PANEL FOR PROPER ALIGNMENT, SEEN TYPICAL NOTES ON AM T.1, FOR ALIGNMENT TOLERANCES.</p> <p>3 - PANELS MUST BE SHIMMED WITH SHIMS MENTIONED IN THE TYPICAL NOTES OF AM T.1, VERIFY SHIMMED PANEL LOCATIONS AND DISTANCES BEFORE INSTALLATION OF FIRST PANEL.</p>		<p>SET FIRST PANELS LEVEL, PLUMB AND ALLOW FOR PROPER INSTALLATION OF ALL PROCEEDING PANELS.</p> <p>1. SCREW BASE ATTACHMENT COMPONENT FIRST (SEE DRAWING).</p> <p>2. AFTER PANEL IS LEVEL, SET AND SECURED SCREW ATTACHMENT.</p> <p>NOTE: START POINT VARIES WITH PROJECT.</p>																
<p>SURFACE TO RECEIVE PANELS</p> <p>THEORETICAL PANEL SURFACE</p> <p>ANY PANEL WIDER THAN 36" REQUIRES A STIFFENER IN EVERY 24"</p>		<p>START POINT</p> <p>DATUM LINE SET PLUMB FOR ALL PANELS</p> <p>A-1</p> <p>DATUM LINE SET LEVEL FOR ALL PANELS</p> <p>1</p> <p>2</p> <p>TEMPORARY PLASTIC CLIPS TO KEEP PANEL SECURED UNTIL BEING INSTALLED.</p>																
STEP 3: FOLLOWING PANEL INSTALLATION		STEP 3: SECOND PANEL ALIGNMENT AND INSTALLATION																
<p>REPEAT INSTALLATION FOR FOLLOWING PANELS. MAINTAIN EQUAL JOINT SPACING THROUGHOUT SYSTEM.</p>		<p>SET SECOND PANEL LEVEL, PLUMB AND ALLOW FOR PROPER INSTALLATION OF ALL PROCEEDING PANELS.</p> <p>SET JOINT BETWEEN PANELS TO AS PER REQUIREMENT .</p> <p>1. REMOVE TEMPORARY PLASTIC CLIP.</p> <p>2. INSTALL THE FOLLOWING PANEL.</p> <p>3. INSERT U-CHANNEL AND SCREW.</p> <p>4. IF IT IS THE LAST PANEL FOLLOW PROCESS #1 IN STEP 2, OTHERWISE, FOLLOW PROCESS #2 IN STEP 2.</p> <p>NOTE: START POINT VARIES WITH PROJECT.</p>																
<p>START POINT</p> <p>A-2</p> <p>A-1</p> <p>A-4</p> <p>A-3</p>		<p>A-2</p> <p>A-1</p> <p>1</p> <p>2</p> <p>3</p>																
STEP 4: GASKET OR BACKER ROD AND SEALANT INSTALLATION		Material Safety Data Sheet																
<p>IF THIS IS DRY SEAL SYSTEM INSTALL THE GASKET TO U-CHANNEL. IF IT'S WET SEAL INSTALL BACKER ROD AND SEALANT. PER MANUFACTURER'S REQUIREMENTS, WHEN INSTALLING GASKET, PLACE A BEAD OF SEALANT OR ADHESIVE IN JOINTS, BEAD TO BE A MINIMUM OF 0'-6" LONG AND PLACED AT ALL JOINTS INTERSECTIONS (IN ALL DIRECTIONS), ALL ENDS OF THE GASKET AND ALL CORNERS (SEE CIRCLES ON DRAWING).</p>		<table><tr><th>Test Method</th><th>Title of Test</th><th>Results</th></tr><tr><td>ASTM E-283</td><td>Air Infiltration 1.60 psf (25 mph) 6.27 psf (50 mph)</td><td><0.01 cfm/ft² = Pass <0.01 cfm/ft² = Pass</td></tr><tr><td>ASTM E-331</td><td>Water Resistance 15.05 psf</td><td>No Leakage</td></tr><tr><td>ASTM E-330</td><td>Uniform Load Deflection (span = 46") +120.0 psf (positive) -80.0 psf (negative)</td><td>0.51" = Pass 0.82" = Pass</td></tr><tr><td>ASTM E-330</td><td>Uniform Structural Load (span = 46") +180.0 psf (positive) -100.0 psf (negative)</td><td>0.02" = Pass 0.18" = Pass</td></tr></table>		Test Method	Title of Test	Results	ASTM E-283	Air Infiltration 1.60 psf (25 mph) 6.27 psf (50 mph)	<0.01 cfm/ft ² = Pass <0.01 cfm/ft ² = Pass	ASTM E-331	Water Resistance 15.05 psf	No Leakage	ASTM E-330	Uniform Load Deflection (span = 46") +120.0 psf (positive) -80.0 psf (negative)	0.51" = Pass 0.82" = Pass	ASTM E-330	Uniform Structural Load (span = 46") +180.0 psf (positive) -100.0 psf (negative)	0.02" = Pass 0.18" = Pass
Test Method	Title of Test	Results																
ASTM E-283	Air Infiltration 1.60 psf (25 mph) 6.27 psf (50 mph)	<0.01 cfm/ft ² = Pass <0.01 cfm/ft ² = Pass																
ASTM E-331	Water Resistance 15.05 psf	No Leakage																
ASTM E-330	Uniform Load Deflection (span = 46") +120.0 psf (positive) -80.0 psf (negative)	0.51" = Pass 0.82" = Pass																
ASTM E-330	Uniform Structural Load (span = 46") +180.0 psf (positive) -100.0 psf (negative)	0.02" = Pass 0.18" = Pass																
<p>NOTE: START POINT VARIES WITH PROJECT.</p>		<p>* Refer to Report No. 96663.02-109-44 performed by Architectural Testing, Inc.</p>																