



ALLIED[®]
SPECIALTY GROUP



Architectural Testing

Performance Test Report
Estolga[®] 3000 Wet Seal Panel System

Section 3 – ASTM Test Results

<u>Test Method</u>	<u>Title of Test</u>	<u>Results</u>
ASTM E-283	Air Infiltration 1.6 psf (25 mph) 4.0 psf (50 mph) 6.24 psf (75 mph)	<0.01 cfm/ft ² = Pass <0.01 cfm/ft ² = Pass <0.01 cfm/ft ² = Pass
ASTM E-331	Water Resistance 12.12 psf	No Leakage
ASTM E-330	Uniform Load Deflection +120.37 psf (positive) -120.37 psf (negative)	<0.01" = Pass <0.01" = Pass
ASTM E-330	Uniform Structural Load +180.56 psf (positive) -180.56 psf (negative)	<0.01" = Pass <0.01" = Pass

* Refer to *Report No. 73801.03-109-44* performed by Architectural Testing, Inc.